

# Quotation

Ref TB-2025-1142

Issued 18 August 2025

Quotation valid until 17 September 2025

Remedial works following damage to boundary wall and garden patio

Customer  
Mr George Bertram Dobbs  
12 Linden Close  
Sheffield  
S11 8AP  
07785 401 119

Site (same)  
12 Linden Close  
Sheffield S11 8AP  
Inspected by: Tim Webb, 17 August 2025

## Scope of work

Site inspected on 17 August 2025. The rear boundary wall (approximately 6 m long, brick on edge with concrete coping) shows stepped cracking and lateral displacement most pronounced at the north-eastern corner. Adjacent garden patio (approximately 14 concrete flags) shows lifting and uneven settlement. Garden path of three rows of paviors shows lifting at the junction with the patio. The cracking and displacement, in our experience, is consistent with root ingress, although we are not surveyors and cannot give a definitive opinion on the cause.

| Description                                                                                                      | Quantity | Rate    | Amount    |
|------------------------------------------------------------------------------------------------------------------|----------|---------|-----------|
| Carefully take down affected section of boundary wall (approx. 4.0 m run) and set aside reusable bricks          | 1 lot    | £420.00 | £420.00   |
| Excavate and break out failed foundation; form 600 mm trench, lay reinforced concrete foundation to 450 mm depth | 4.0 m    | £155.00 | £620.00   |
| Rebuild boundary wall in matching reclaimed brick (3 courses high) including coping                              | 4.0 m    | £190.00 | £760.00   |
| Lift, prepare bed and relay 14 concrete patio flags; install drainage channel to lowest point                    | 14 No.   | £62.00  | £868.00   |
| Re-set garden path (paviors) at junction with patio                                                              | 3.0 m    | £86.00  | £258.00   |
| Materials: cement, sand, ballast, reinforcement mesh, joint sand, sealant                                        | 1 lot    | -       | £284.00   |
| Skip hire, plant and waste removal                                                                               | 1 wk     | -       | £190.00   |
| Site clearance, snag list and reinstatement                                                                      | 1 lot    | -       | £100.00   |
| Subtotal (ex VAT)                                                                                                |          |         | £3,500.00 |
| VAT @ 20%                                                                                                        |          |         | £700.00   |
| Total (inc. VAT)                                                                                                 |          |         | £4,200.00 |

Note. Our remit is to put right the damage we have been asked to remedy. We are not chartered surveyors or arboriculturists and the assessment above of likely cause (root ingress) is offered on the basis of practical building experience only.

## Payment terms

Account name: Trentham Builders Ltd

Sort code: 60-09-12 Account no.: 38271544

Reference: TB-2025-1142

Payment terms (if instructed): payment due 30 days from completion. Cards accepted by phone (small surchar